

**ADDENDUM NO. 2****PROJECT: PHASE A INFRASTRUCTURE IMPROVEMENTS**

To: Prospective Bidders of Record

Date: October 18, 2017

---

The following changes, additions, revisions, and/or deletions are hereby made a part of the Contract Documents for the aforementioned Project as fully and completely as if the same were fully set forth therein:

**A. PART 1 – CONTRACT REQUIREMENTS**

1. Section EJCDC C-451, Qualifications Statement, Page 7 of 7: DELETE the following:

“7. Required safety program submittals listed in Section 13.”

**B. PART 2 – SPECIFICATIONS**

None.

**C. PART 3 – DRAWINGS**

1. Sheet C-300, Gerrardstown Site Plan: ADD new Note 11 as follows:

“11. Provide a minimum of 6” of #57 stone for the access driveway and parking area to the limits shown. Prior to placing stone, compact subgrade to not less than 95% maximum density.”

**END OF ADDENDUM NO. 2**

## WRITTEN QUESTIONS FROM BIDDERS AND ANSWERS

The following questions and the *answers* by the Owner are for informational purposes only and are not considered part of the Contract Documents. The questions below are those received by the Owner from October 12, 2017 through 11:00 a.m. on October 18, 2017. Prior questions 1-8 are attached to the Addendum No. 1 Document. The information provided below shall not modify or amend the Contract Documents.

9. Please clarify the restoration required at the Pikeside Booster Pump Station. The drawings show a 12' wide access road to the gate. Is the remaining area inside the fence to be asphalt as well?

*A9: The restoration for Pikeside is to be grass. All paved areas inside and outside the fence are shown on the plans and are to be asphalt, and the rest of the area is to be restored to grass. The 12' wide asphalt access road ties into Evans Run Drive and extends inside the fence as shown on Sheet C-200.*

10. Please clarify the restoration required inside the fence and the new access road at the Gerrardstown Booster Station.

*A10: At Gerrardstown, the driveway and parking area (both inside and outside the fence) will be stone. All other areas inside the fence that are not stone are to be restored with grass. See clarification provided via Addendum No. 2.*

END OF WRITTEN QUESTIONS AND ANSWERS